FINISH SCHEDULE KEY

CODE	MATERIAL	MANUFACTURER	STYLE	SIZE	COLOR	CONTACT INFO	NOTES
CT-1	CERAMIC TILE	VITL COMMERCIAL SOLUTIONS	BASELINE	4" X 12" TILES	#VTLBATA412G TAUPE GLOSSY		INSTALLATION METHOD = 1/3 OFFSET STANDRD RUNNING BOND, GROUT TO BE TEC POWER GROUT COLOR #931 STANDARD WHITE
CT-2	CERAMIC TILE	TILEBAR	LOS LUNAS	4" X 12" TILES	WHITE		INSTALLATION METHOD = 1/3 OFFSET STANDRD RUNNING BOND, GROUT TO BE TEC POWER GROUT COLOR #988 PEARL
IPS-1	PAINT (TO MATCH)	SHERWIN WILLIAMS	EGGSHELL	-	#7551 GREEK VILLA		MAIN PAINT COLOR
IPS-3	PAINT (TO MATCH)	SHERWIN WILLIAMS	EGGSHELL	-	#7757 HIGH REFLECTIVE WHITE		CEILING PAINT COLOR
IPS-4	PAINT (TO MATCH)	SHERWIN WILLIAMS	EGGSHELL	-	#6994 GREENBLACK		DOOR AND TRIM PAINT COLOR
PL-1	PLASTIC LAMINATE	WILSONART	38 FINE VELVET TEXTURE	38 FINE VELVET TEXTURE	#7992 PINNACLE WALNUT		
PT-1	PORCELAIN TILE	VITL COMMERCIAL SOLUTIONS	SWINDON	12" X 24" X .33" THICK TILES	#VTLSWYO1224R YORK		BATHROOM FLOORING
SS-1	SOLID SURFACE	WILSONART	EASED EDGES	-	#9913SS CALACATTA PERLATO		
SS-2	SOLID SURFACE	WILSONART	EASED EDGES	-	#9196RS YUKON RIVERSTONE		
WDB-1	WOOD BASEBOARD	ELENBAAS	BEADED BASE	1/2" X 4"	IPS-4		REFER TO SHEET A310 FOR DETAILS
WDT-1	WOOD TRIM	-	-	-	IPS-4		REFER TO SHEET A310 FOR TRIM DETAILS

FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALL				CEILING	MILLWORK		NOTES
				NORTH	EAST	SOUTH	WEST		CABINET	TOP	
100	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX
101	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX
102	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX	WHITE BOX
103A	LIVING/ KITCHEN	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1/CT-2	IPS-1/CT-2	IPS-1	IPS-3	PL-1	SS-1	CT-2 AS BACKSPLASH
103B	W/D	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
103C	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
103D	BATH	PT-1	IPS-4	IPS-1/CT-1	IPS-1/CT-1	IPS-1/CT-1	IPS-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
103E	CLOSET	PT-1	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
103F	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
103G	BEDROOM	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	EXISTING BRICK	IPS-1	IPS-3			
104A	LIVING/ KITCHEN	SEE GENERAL NOTE 8	IPS-4	IPS-1/EXISTING BRICK	IPS-1/CT-2	IPS-1/CT-2	IPS-1	IPS-3	PL-1	SS-1	
104B	W/D	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
104C	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
104D	BATH	PT-1	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
104E	BEDROOM	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	EXISTING BRICK	IPS-1	IPS-3			
104F	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	EXISTING BRICK	IPS-1	IPS-3			
105A	LIVING/ KITCHEN	SEE GENERAL NOTE 8	IPS-4	IPS-1/EXISTING BRICK	EXISTING BRICK	IPS-1/CT-2	IPS-1/CT-2	IPS-3	PL-1	SS-1	CT-2 AS BACKSPLASH
105B	CLOSET	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	IPS-1	IPS-1	IPS-3			
105C	W/D	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
105D	BATH	PT-1	IPS-4	IPS-1	IPS-1	IPS-1/CT-1	IPS-1/CT-1	IPS-3	PL-1	SS-2	
105E	BEDROOM	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	EXISTING BRICK	IPS-1	IPS-3			
105F	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
106	WEST STAIR	SEE GENERAL NOTE 18	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
107	BASEMENT STAIR	SEE GENERAL NOTE 18	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
108	EAST STAIR	SEE GENERAL NOTE 18	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3			
200A	LIVING/ KITCHEN	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1/CT-2	IPS-1	EXISTING BRICK	IPS-3	PL-1	SS-1	CT-2 AS BACKSPLASH
200B	MECH	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	EXISTING BRICK	IPS-1	IPS-3	-	-	
200C	W/D	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	EXISTING BRICK	EXISTING BRICK	IPS-3	-	-	
200D	CORRIDOR	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	-	IPS-1	IPS-3	-	-	
200E	BATH 1	PT-1	IPS-4	IPS-1/CT-1	IPS-1	IPS-1/CT-1	IPS-1/CT-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
200F	BEDROOM 1	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	EXISTING BRICK	IPS-3	-	-	
200G	CLOSET	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	IPS-1	EXISTING BRICK	IPS-3	-	-	
200H	BEDROOM 2	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
200I	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
200J	CL.	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
200K	BATH 2	PT-1	IPS-4	IPS-1/CT-1	IPS-1/CT-1	IPS-1	IPS-1/CT-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
201A	CORRIDOR	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
201B	KITCHEN	SEE GENERAL NOTE 8	IPS-4	-	IPS-1/CT-2	IPS-1	IPS-1/CT-2	IPS-3	PL-1	SS-1	CT-2 AS BACKSPLASH
201C	LIVING	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	-	IPS-1	IPS-3	-	-	
201D	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
201E	W/D	PT-1	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
201F	BATH	PT-1	IPS-4	IPS-1/CT-1	IPS-1/CT-1	EXISTING BRICK/CT-1	IPS-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
201G	BEDROOM	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
201H	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
202A	CORRIDOR	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	EXISTING BRICK	IPS-1	IPS-1	IPS-3	-	-	
202B	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
202C	BEDROOM	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
202D	BATH	PT-1	IPS-4	IPS-1/CT-1	IPS-1	IPS-1/CT-1	IPS-1/CT-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
202E	LIVING/ KITCHEN	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	EXISTING BRICK	IPS-1/CT-2	IPS-1/CT-2	IPS-3	PL-1	SS-1	CT-2 AS BACKSPLASH
202F	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
202G	W/D	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
203A	KITCHEN	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1/CT-2	IPS-1	IPS-1	IPS-3	PL-1	SS-1	CT-2 AS BACKSPLASH
203B	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
203C	W/D	PT-1	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
203D	BATH	PT-1	IPS-4	IPS-1	IPS-1/CT-1	IPS-1/CT-1	IPS-1/CT-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
203E	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
203F	BEDROOM	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
203G	LIVING	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
203H	CL.	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
204A	CORRIDOR	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
204B	BEDROOM	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
204C	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
204D	KITCHEN	SEE GENERAL NOTE 8	IPS-4	-	IPS-1/CT-2	IPS-1	IPS-1/CT-2	IPS-3	PL-1	SS-1	CT-2 AS BACKSPLASH
204E	LIVING	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
204F	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
204G	BATH	PT-1	IPS-4	IPS-1/CT-1	IPS-1/CT-1	IPS-1/CT-1	IPS-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
204H	W/D	PT-1	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
205A	LIVING/ KITCHEN	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	IPS-1	IPS-1/CT-2	IPS-1/CT-2	IPS-3	PL-1	SS-1	CT-2 AS BACKSPLASH
205B	BEDROOM	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
205C	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
205D	BATH	PT-1	IPS-4	IPS-1/CT-1	IPS-1	IPS-1/CT-1	IPS-1/CT-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
205E	W/D	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
206A	LIVING/ KITCHEN	SEE GENERAL NOTE 8	IPS-4	EXISTING BRICK	EXISTING BRICK/CT-2	IPS-1/CT-2	IPS-1	IPS-3	PL-1	SS-1	CT-2 AS BACKSPLASH
206B	MECH	SEE GENERAL NOTE 8	IPS-4	IPS-1	EXISTING BRICK	IPS-1	IPS-1	IPS-3	-	-	
206C	W/D	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
206D	BATH	PT-1	IPS-4	IPS-1/CT-1	IPS-1/CT-1	IPS-1	IPS-1/CT-1	IPS-3	PL-1	SS-2	CT-1 ON SHOWER WALLS
206E	BEDROOM	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	EXISTING BRICK	IPS-1	IPS-3	-	-	
206F	CLOSET	SEE GENERAL NOTE 8	IPS-4	IPS-1	EXISTING BRICK	EXISTING BRICK	IPS-1	IPS-3	-	-	
207	MECH	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
208	MECH	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
209	MECH	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	IPS-1	IPS-1	IPS-3	-	-	
210	HALLWAY	SEE GENERAL NOTE 8	IPS-4	IPS-1	IPS-1	EXISTING BRICK	IPS-1	IPS-3	-	-	

NOT IN SCOPE

ON ALL FINISH PLANS, NORTH IS TO BE ASSUMED DIRECTLY STRAIGHT UP ON THE FLOOR PLAN TO CORRELATE WITH WALL FINISH LOCATIONS

GENERAL NOTES

1. PROJECT NORTH FOR ALL FINISH PLANS SHALL BE LOCATED AT THE TOP OF THE DRAWING AREA, UNLESS OTHERWISE NOTED.
2. CONTRACTOR SHALL SUBMIT SAMPLES OF ALL SPECIFIED FINISH MATERIALS FOR SUBMITTAL REVIEW AND FINAL APPROVAL PRIOR TO ORDERING AND INSTALLATION.
3. ALL FURNITURE SHOWN ON PLANS IS FOR REFERENCE, SCALE, SPACE PLANNING AND ELECTRICAL/DATA CONNECTION LOCATION PURPOSES, ONLY. ALL FURNITURE (INCLUDING SPECIALTY ITEMS, SUCH AS DISPLAY CASES) SPECIFICATION, SELECTION, PROCUREMENT AND INSTALLATION SHALL NOT BE PART OF SCOPE OF WORK FOR BUILDING CONTRACTOR.
4. PRIME AND PAINT ALL SURFACES WITH A MINIMUM (2) FINISH COATS.
5. AS NOTATED ON FINISH PLANS, CONTRACTOR TO PROVIDE AND INSTALL GLAZED CERAMIC WALL TILE (WITH CERAMIC TILE BASE) FROM FLOOR TO CEILING AT 'WET WALL' LOCATIONS. GROUT FOR ALL TILE INSTALLATIONS SHALL BE TEC POWER GROUT OR APPROVED EQUAL. REFER TO MATERIAL SELECTION SCHEDULE FOR TILE STYLE/ COLOR AND GROUT COLOR.

FLOORS

6. FOR PROJECTS THAT HAVE CONCRETE SLAB ON GRADE AS EXISTING CONDITIONS OR NEW POUR, CONTRACTOR SHALL CONDUCT REQUIRED MOISTURE TESTS PRIOR TO INSTALLATION OF ALL SPECIFIED NEW FLOOR FINISH MATERIALS. RECORD PASSING MOISTURE LEVELS PRIOR TO START OF INSTALLATION. REFERENCE MANUFACTURERS INSTALLATION SPECIFICATIONS FOR EACH FLOOR FINISH TYPE TO VERIFY REQUIREMENTS
7. CONTRACTOR TO PROVIDE AND INSTALL ALL REQUIRED TRANSITIONS STRIPS, AS DETAILED ON FINISH PLANS. ALL FLOORING TRANSITIONS/ TRANSITION STRIPS SHALL BE CENTERED UNDER DOORS WHEN THEY ARE IN THE CLOSED POSITION OR CENTERED BETWEEN ROOM OPENINGS, UNLESS OTHERWISE NOTED. CONTRACTOR SHALL UTILIZE ANY NECESSARY AMOUNT OF LEVELING COMPOUND AT ALL UNEVEN SUBFLOOR CONDITIONS SO THAT THE APPROPRIATE HEIGHT TO ENSURE A FLUSH AND EVEN TRANSITION BETWEEN ADJACENT FLOOR MATERIALS IS ACHIEVED AND MAINTAINED THROUGHOUT ROOM. TRANSITION STRIPS (TS-1) BETWEEN EXISTING FLOOR AND PT-1 TO BE TARKETT JOHNSONITE CTA 31 P 3/8" MATERIAL TO SUBFLOOR 31 ZEPHYR.
8. ALL EXISTING WOOD FLOORS ARE TO BE RESURFACED AND REFINISHED USING MINIWAX PERFORMANCE SERIES TINTABLE WOOD STAIN, COLOR HABITAT #MW427. TEST SAMPLE OF COLOR FOR OWNER APPROVAL. PROVIDE PROTECTIVE TOPCOAT PRIOR TO FINISHED CONSTRUCTION. KEEP PLANKS FOR REPLACEMENT.
-IF FLOORS ARE FOUND DAMAGED, FLOORS TO BE PATCHED PRIOR TO REFINISHING.

WALLS

9. CONTRACTOR TO PAINT ALL BULKHEADS TO MATCH SURROUNDING WALL PAINT SELECTION ON FACE AND UNDERSIDE OF EACH BULKHEAD, UNLESS NOTED OTHERWISE.
10. ALL EXTERIOR WALL HISTORIC TRIM TO REMAIN OR BE REPLICATED

CEILINGS

11. CONTRACTOR TO PAINT ALL BULKHEADS TO MATCH SURROUNDING WALL PAINT SELECTION ON FACE AND UNDERSIDE OF EACH BULKHEAD, UNLESS NOTED OTHERWISE.
12. CONTRACTOR SHALL PAINT ANY EXPOSED CONDUIT, PIPING, JUNCTION BOXES, DUCTWORK AND OTHER EXPOSED UTILITIES AT EXPOSED CEILING LOCATIONS PAINT SHALL FOR THESE EXPOSED ITEMS SHALL MATCH SPECIFIED CEILING PAINT, OTHER THAN IN MECHANICAL AND ELECTRICAL ROOMS.

MILLWORK

13. CONTRACTOR TO PROVIDE AND INSTALL DOOR AND DRAWER PULLS FOR SPECIFIED CABINETRY. PULLS FOR CABINETRY SHALL BE RICHELIEU TRANSITIONAL METAL PULL - 8695, FINISH MATTE BLACK - BASIS OF DESIGN. ALL WALL CABINET PULLS SHALL BE INSTALLED VERTICALLY, MOUNTED TO THE LATCH SIDE OF WALL CABINET DOORS. CENTER OF DRAWERS (U.N.O.) ALL DRAWER PULLS ARE SHOWN FOR REFERENCE ONLY AND IS NOT AN INDICATION OF EXACT MOUNTING LOCATION.
14. FOR ALL EXPOSED METAL COUNTERTOP SUPPORTS, CONTRACTOR TO PAINT IN FIELD WITH SAME PAINT COLOR AS SURROUNDING WALL FINISH. PAINT SHALL BE AN ALKYD WITH SEMI-GLOSS FINISH, UNLESS OTHERWISE NOTED.
15. ALL EXPOSED METAL ELEC./MECH. ITEMS IN OCCUPIED SPACES TO BE FIELD-PAINTED TO MATCH SURROUNDING WALL FINISH. ALL ELECTRICAL PLUGS, SWITCHES AND CORRESPONDING COVERPLATES SHALL BE WHITE.

MISC.

16. ALL SOLID SURFACE, GRANITE OR OTHER NATURAL STONE SURFACES (COUNTERTOPS, BACKSPALSHES, WINDOW SILLS, ETC.) SHALL HAVE FINISHED EASED EDGES.
17. PROVIDE A SMOOTH LEVEL 4 DRYWALL FINISH ON ALL GYPSUM WALLS U.N.O.
18. ALL JANITOR CLOSETS OR ROOMS WITH A MOP SINK OR SERVICE SINK SHALL HAVE FIBER REINFORCED PANEL (FRP) INSTALLED FROM TOP OF WALL BASE TO 4'-0" A.F.F. WITHIN 4' OF SINK FIXTURE.
19. REFINISH ALL STAIRS, STAIR TREADS, AND STAIR RISERS WITH MINIWAX PERFORMANCE SERIES TINTABLE WOOD STAIN, COLOR HABITAT #MW427. TEST SAMPLE OF COLOR FOR OWNER APPROVAL. PROVIDE PROTECTIVE TOPCOAT PRIOR TO FINISHED CONSTRUCTION. KEEP PLANKS FOR REPLACEMENT.

FINISH PLAN LEGEND

CT-1

CT-2

TS-1: REFER TO GENERAL NOTE 7

© 2023 Driven Design Studio, All Rights Reserved.

DRIVEN DESIGN

ARCHITECT
Driven Design Studio PLLC
117 West Michigan Avenue
Battle Creek, MI 49017
(269) 753-8040
cody@drivendesignstudio.com

THIS DOCUMENT IS THE EXCLUSIVE PROPERTY OF DRIVEN DESIGN. THE DOCUMENT & THE INFORMATION IT CONTAINS MAY NOT BE REPRODUCED OR USED FOR OTHER THAN THE SPECIFIC PROJECT FOR WHICH IT WAS PREPARED WITHOUT THE EXPLICIT CONSENT OF DRIVEN DESIGN.

PROJECT NAME
101 S MAIN EVART

PROJECT ADDRESS
101 S. MAIN ST, EVART, MI

CLIENT

ISSUE
CONSTRUCTION DOCUMENTS

REVISION

DRAWN BY CMN

DATE 12/2/2025 11:54:54 AM

SCALE 1/4" = 1'-0"

STAMP

PROJECT NUMBER
2025.072

FINISH SCHEDULE

A140